

**Toilet Consturctuon fo Shangri-La International School (SIS)**  
**Quoation Form**  
**2020**

**Company Profile**

Company Name:

Address

Company Registration No:

Caontact No

Tax Clarance

Completed

Not Completed

Contact Person:

**Detail rate**

SN	Work Description	unit	Total Qty	Unit Rate	Total Amount	Remarks
<b>A.</b>	<b>Dismantle Works</b>					<b>Total estimated cost is RS 150000</b>
1	Breaking of RCC slab and beams and disposing it up to 30m	cft	537			
2	Breaking of Brickwork made in C/S mortar cleaning it and storing it up to 30m.	cft	991			
3	Removing the brickwork from foundation and storing it upto 30m	cft				
	<b>Total</b>					
<b>B.</b>	<b>Temporary toilet</b>					<b>Total Estimated Cost is RS 100000</b>
1	Preparing 4 nos of temporary Toilet using bamboo and CGI sheet for walls and Roof as prescribed by the supervisor, and fitting 4 Pans all complete as per instruction	L/S	4			
2	Preparing temporary septic tank using 4' Dia well rings, digging and placing all complete as per instruction	nos	20			
	<b>Total</b>					
<b>C.</b>	<b>Construction of New Toilet</b>					<b>Total Estimated Cost is RS 2,740,000</b>
1	<b>Earthwork in Excavation</b>					
	a) Earth Excavation in hard soil or as per site condition and carrying the earth up to 30m outside or inside of site.	C.Ft.	28531.56			
2	<b>One layer Flat Brick soling</b>					
	One layer Flat Brick soling in foundation and inside toilets in perfect line, level and thickness as per instruction	sqft	1564.83			
3	<b>P.C.C. (1:3:6)</b>					
	Preparing mixing and laying of Plain cement concrete in Foundation and inside toilets using prescribed brand of cement and aggregates all complete as per drawing and instruction from supervisor	C.Ft.	230.27			
4	<b>R.C.C. works</b>					
	a) M20 plain cements concrete of 1:1.5:3 for R.C.C. works with cement, sand and aggregate including mixing, laying and curing of the concrete as per specification.	C.Ft.	245.03			

<b>5</b>	<b>Formwork (Fairface using plywood)</b>					
	Formwork shuttering for any shape and size of lintels bands and beams works as per design and instruction of Engineer. Scaffolding, fixing etc, for formwork all cost to included	Sq.Ft.	835			
<b>6</b>	<b>Reinforcement Steel</b>					
	TMT Rebar of Fe500 grade including straightening, cleaning, bending, cutting and fixing in position of any shape and size with 20BG annelaled tying GI wire as per drawing and specification.	Kgs.	1498.451			
<b>7</b>	<b>Brickwork</b>					
	Brickwork constructed with 1st class chimney bhatta brick of uniform size in cement sand mortar in 1:6 or 1:4 ratio as per specification for substructure with preparation of cement mortar , laying and curing the whole work all complete.	cft	1441.65			
	Dry Interlock Brickwork constructed with Standard Interlock brick of uniform size for superstructure with preparation of lime mortar (1:3) for void filling , laying and curing the whole work all complete.	cft	921.92			
<b>8</b>	<b>CGI sheet Roof</b>					
	Preparing CGI sheet Roof with Coloured CGI Sheet of known brand and thickness in Borax Treated Bamboos with metal Plate Stiffners all complete as per drawing and instruction from the supervisor.	sqft	1048.464			
<b>9</b>	<b>Plaster works</b>					
	Plastering with specified mortar mix ratio in any level, size and shape of wall, band, blocks etc. as required including racking, watering cleaning of base , platering to plumb, line, level, smoothness etc. and including curing and cost of necessary scaffoldings works all complete as per drawings and specifications.					
	A) 20 mm thick C/S (1:6) plaster on external walls	sqft	364.65			
	B) 12.5 mm thick C/S (1:4) plaster on internal walls	sqft	759.26			
	C) 2mm thick punning	sqft	214.03			
<b>10</b>	<b>Tile works</b>					
	Supplying and Laying 10mm thick normal standard porecelyne glazed Tile with 1:4 cement sand mortar					
	In walls	sqft	1185.56			
	in floors	sqft	602.7			
<b>11</b>	<b>Painting works</b>					
	Supplying and whitewashing the wall surfaces with 2 coats of white cement as per instruction	sqft	1123.91			
	Supplying and painting the Interior and exterior wall surface with two coat of paint of approved brand and uniform shade.	sqft	1123.91			
<b>12</b>	<b>Wooden Doors</b>					
	Supplying and fixing wooden frame of DOOR with necessary fittings all complete	cft	24.63			
<b>13</b>	<b>Pipe fitting</b>					
	complete pan and sanitation fitting work					
<b>14</b>	<b>Electric work</b>					

	complete wirring with materials					
	Total					
	Grand Total				<b>0.00</b>	<b>Rupees</b>
	<b>Total Amount :</b>	<b>0.00</b>				